



# LOT 69 EASTMANS GREEN SUBDIVISION NEWSTEAD

## GEOTECHNICAL SUMMARY

In general accordance with AS1726 (1993) *Geotechnical Site Investigations*

## SITE (“SOIL TEST”) CLASSIFICATION

In general accordance with AS2870 (2011) *Residential slabs and footings*

AND

## WIND LOAD CLASSIFICATION

In general accordance with AS4055 (2006) *Wind loads for housing*




  
eastmans green  
take the first step

Newstead, Tasmania





### The Eastmans Green Subdivision and its 5 stages





## Geotechnical summary

Risks associated with a variety of geotechnical issues on and near Lot 69 Eastmans Green Subdivision, Newstead range from Very Low to High. This is a normal situation for many undeveloped hillsides in Launceston. Provided the recommendations in Attachment 1, and in the Table on the next page, are followed, the risks will be reduced to, and will remain mostly in, the Very Low – Low range during and after residential development.

## AS2870 Site Classification

In accordance with Australian Standard 2870 (2011) *Residential slabs and footings*, the area **abcd** shown on the accompanying site plan of Lot 69 Eastmans Green Subdivision, Newstead is classified as **Class P**.

Class P sites require footings designed by engineering principles.

## AS4055 Wind Classification

In accordance with Australian Standard 4055 (2006) *Wind loads for housing*, the following wind load classification is made for a house site on Lot 69 Eastmans Green Subdivision, Newstead:

|                                 |  |
|---------------------------------|--|
| Wind Region                     | <b>A</b>   |
| Terrain Category classification | <b>TC3</b>   |
| Topographic classification      | <b>T1</b>  |
| Shielding classification        | <b>PS</b>  |
| Wind classification             | <b>N1</b>  |
| Max. Design Gust Wind Speed     | <b>26m/s</b> [Serviceability limit state ( $V_{h, s}$ )]<br><b>34m/s</b> [Ultimate limit state ( $V_{h, u}$ )] |

**W. C. Cromer**

**Principal**

22 August 2014

**PART 1 of this AS2870 assessment is this report accompanied by the following Attachments:**

- Attachment 1. Summary of geotechnical issues, consequences and risks to house site, before and after management of the risks
- Attachment 2. Title plan
- Attachment 3. Excavation logs of test pits
- Attachment 4. Site and test pit photographs
- Attachment 5. Good and poor hillside construction practices
- Attachment 6. Important notes about this report

**PART 2 of this AS2870 assessment contains important additional geotechnical information** in a separate report entitled *Geotechnical Notes to accompany AS2870 ("soil test") reports for individual lots, Eastmans Green Subdivision, Newstead*. It is freely available on-line at <http://eastmansgreen.com.au/> and <http://www.williamccromer.com/> and hard copies are available on request free of charge.

Stakeholders shall consider both Part 1 and Part 2 for the development of this lot.





## Summary of geotechnical information for this Lot

|                                     |   |
|-------------------------------------|---|
| <b>Test pits dug</b>                | 69A, 69B  |
| <b>Photographs</b>                  | Of each pit and excavated materials   |
| <b>Dumpy levelling</b>              | Pits relative to each other and to lot boundary pegs  |
| <b>DCP profiles</b>                 | 2; range 1 to 22 blows/100mm  |
| <b>Shear vane readings</b>          | 8; range 44 to 228kPa   |
| <b>Shrink-swell tests</b>           | 2. Iss = 5.0% @0.6 - 0.9m, and 2.8% @ 1.1 - 1.4m, both in pit 69A   |
| <b>Est. ground surface movement</b> | 60mm in pit 69A, 40mm in pit 69B, based on Iss and soil profile   |
| <b>AS2870 site classification</b>   | Class H2 based on test pit profiles, inside area abcd on site plan  |
| <b>Dispersion tests</b>             | 1; Emerson Class #3 (dispersive when remoulded)   |
| <b>Fill</b>                         | 0.1m in pit 69A, thickening upslope to about 1.1m in pit 69B; note, however, presence of drainage easement (sewer pipe is about 5m deep across the lot; expect variable thickness across upper parts of lot |
| <b>Soils</b>                        | 0.7m thick in pit 69A; absent in pit 69B  |
| <b>Geology</b>                      | Weakly cemented sandstone; claystone  |
| <b>Groundwater</b>                  | None encountered  |
| <b>Subsurface conditions</b>        | Clay and claystone in pit 69A; disturbed ground in pit 69B on extremely weathered sandstone   |
|                                     | Reactive clays present in area abcd, but depth and thickness expected to be variable  |
|                                     | Bearing capacities variable; adequate below 1m or so; strength increases with depth   |
|                                     | Risk of settlement low based on in-situ strength testing. See test pit logs   |
|                                     | Risk of slope instability low conditional on Recommendations below and in Attachment 1.   |


### Recommendations

|                                 |   |
|---------------------------------|---|
| <b>General</b>                  | Adopt good hillside construction practices (Attachment 5). Keep records/photographs of all construction stages (Attachment 6).  |
| <b>General</b>                  | Avoid loading the slope unnecessarily, at all scales. Consider building with flexible, light-weight materials.  |
| <b>Test pits</b>                | Locate backfilled test pits; design footings to avoid them  |
| <b>Footings</b>                 | Piers through fill to materials of adequate bearing capacity.   |
| <b>Footing target and depth</b> | Recommended target is claystone at >1.5m near pit 69A; weathered sandstone may be present below 2m closer to pit 69B  |
| <b>Footings inspection</b>      | Engineering inspection desirable  |
| <b>Excavations</b>              | Avoid excavations or minimise height and number. Support all excavations higher than about 0.8m with engineered, drained retaining walls. Construct upslope cut-off drains. All drains to discharge to stormwater system.   |
| <b>Use of fill</b>              | Avoid using fill as a weight bearing material, unless its placement is controlled. Batter angles to be gentler than 1 vertical:2 horizontal   |
| <b>Access drives</b>            | Where the grades of access drives exceed about 15% (8.5°), the access should be constructed with asphalt or concrete surfaces.  |
| <b>Services</b>                 | All water and sewer services should be in flexible pipework, laid in trenches aligned up and down the slope as far as possible. All trenches to be backfilled with clayey materials (not screened gravel). Where stormwater or sewer pipes are constructed on grades greater than 15% (8.5°), they should be constructed with anchors to prevent movement down the slope. |
| <b>Revegetating</b>             | Do not plant large trees closer to the house than the height of the mature tree   |
| <b>Subsurface issues</b>        | Contact Bill Cromer (0408 122 127; billcromer@bigpond.com) if unexpected site or subsurface conditions are found. Take photographs of the conditions.   |





## Site plan and cross section



### WARNINGS

The contour lines shown in this site plan have been obtained from 2008 1m LiDAR, and have since probably been altered by cut and fill.

An indication of the depth of fill (if fill is present) can be obtained from the test pit logs in this report, and by comparing the 1m contour map generated from the 2008 1m LiDAR with detailed surveys of the current land surface.

Purchasers of lots are advised to commission a survey check of lot dimensions and a detail survey.

Fill depth may be extremely variable across a lot, and across a single house footprint. The distribution of fill may be different from that indicated in test pit logs, or on this site plan.

Excavated backfill in test pits is uncontrolled, low strength and prone to settlement. Designers and builders must take account of test pit locations in footing design and placement.



Surveyed peg with grid coordinates. XY data file (to 3 decimal places, but rounded to one) supplied by D. J. McCulloch & Associates, Surveyors, Riverside. Grid and all other features added by William C Cromer Pty Ltd. is the section line on the next page.

Pre-subdivision contours (mASL) at 1m intervals, from LiDAR coverage based on the 2008 Climate Futures. Prospective or actual land purchasers are strongly advised to do a detail survey of the lot prior to building design to (a) establish that survey pegs as shown are accurately located, and (b) compare the pre-subdivision contours shown here with present-day contours to estimate the extent and depth of ground disturbance (cut or fill) to assist in footing and house design.

Areas inferred to comprise controlled fill other than sand and deeper than 0.4m, and/or uncontrolled fill deeper than 0.8m for sand and 0.4m for material other than sand,



Numbered excavator test pit, approximately drawn to scale. Black dot is deepest part of pit. The alignment of the long axis of the pit is shown as degrees true (°T). Distances from deepest part of pit (black dot) to pegs or other indicated features are accurate to 0.3m. [It will be important to relocate the backfilled test pit(s), and their deepest points, so that the ground disturbance they caused can be accounted for in footing design and location.]

The green figure (where present) is an arbitrary elevation of 50.0m for the ground surface at (one of) the test pit(s). (No surveyed elevations are available). Other green figures are dummy-levelled elevations relative to the test pit. Assume elevations are accurate to about 0.1m.



D = Disturbed sample collected; U = Undisturbed sample collected; DCP = Dynamic cone penetrometer profile done






**A**

**B**

Lot 69 Cross section A – B (natural scale)

Inferred fill deeper than 0.8m for sand and 0.4m for material other than sand. Thickness shown here is based on site surface observation, exposures in test pits, and the 1m 2008 LIDAR contours. Ground surface was not surveyed other than at pits 69A and 69B.




— Pre-subdivision (2008) surface — Present day (July 2014) surface (approx)

Drainage easement with sewer pipe (diam. and depth uncertain)

**Checklist for AS2870 site classification**

In accordance with AS2870:2011 *Residential slabs and footings*





## Attachment 1

### Summary of geotechnical issues, consequences and risks to house site on Lot 69, before and after management of the risks

| Issue #                     | Issue | Before treatment   |                          |                           | Recommended risk treatment | After treatment   |                          |                           |                 |
|-----------------------------|-------|--|--------------------------|---------------------------|----------------------------|---|--------------------------|---------------------------|-----------------|
|                             |       | Likelihood of occurrence   | Consequences to property | Level of risk to property |                            | Likelihood of occurrence  | Consequences to property | Level of risk to property |                 |
| Landslide/slope instability | 1     | Rotational or translational deep seated earth or debris slide. Refer to Attachment 4 in PART 2.  | Barely Credible          | Minor to Major            | Very Low to Low            | None  | Barely Credible          | Minor to Major            | Very Low to Low |
|                             | 2     | Rotational or translational shallow earth or debris slide. Refer to Attachment 4 in PART 2.  | Possible to Unlikely     | Minor to Medium           | Low to Moderate            | Control stormwater discharge. Incorporate good hillside construction practices. Avoid or minimise excavations. Support excavations with engineered, drained retaining walls designed to resist lateral movement. Ensure fill placement is controlled. See Attachment 5. | Unlikely                 | Minor                     | Low             |
|                             | 3     | Translational earth or debris slide, fall or topple: Very small scale; on steep, unsupported (artificial) excavations. Refer to Attachment 4 in PART 2.  | Likely to Almost Certain | Minor                     | Moderate to High           | As for Issue 2  | Unlikely                 | Minor                     | Low             |
|                             | 4     | Rotational or translational earth or debris slide: Very small to small scale; shallow, in fill (eg beneath or next to houses; on the outside of access drives). Refer to Attachment 4 in PART 2. | Possible to Likely       | Medium                    | Moderate to High           | As for Issue 2  | Unlikely                 | Insignificant to Minor    | Very Low to Low |
|                             | 5     | Earth or debris flow: Very small to small scale; shallow; in soil and/or uncontrolled fill. Refer to Attachment 4 in PART 2.   | Unlikely                 | Minor                     | Low                        | As for Issue 2  | Unlikely                 | Minor                     | Low             |
|                             | 6     | Soil creep. Refer to Attachment 4 in PART 2.   | Barely Credible          | Minor                     | Very low                   | As for Issue 2  | Barely Credible          | Minor                     | Very low        |





### Summary of geotechnical issues (continued)

|    |  | Before treatment                                      |                         |                  |  | After treatment                                       |                         |                 |
|----|--|---|-------------------------|------------------|--|---|-------------------------|-----------------|
|    |  |   |                         |                  |  |   |                         |                 |
| 7  | Surface soil erosion   | Possible  | Minor                   | Moderate         | As for Issue 2. Revegetate (but no large trees close to house (see below)  | Unlikely  | Minor                   | Low             |
| 8  | Tunnel erosion (dispersive soils)  | Unlikely  | Medium                  | Low              | As for Issue 2. Revegetate (but no large trees close to house (see below)  | Unlikely  | Minor                   | Low             |
| 9  | Foundation movement (eg settlement) due to low strength materials (eg uncontrolled fill, soft soils) | Possible  | Medium                  | Moderate         | Pier all footings for house through any fill identified during construction. Refer to accompanying site plan.  | Unlikely  | Minor                   | Low             |
| 10 | Foundation movement due to reactive or unstable soils  | Likely  | Medium                  | High             | As for Issue 9 and 11. Control drainage. Avoid ponding of water against buildings. Avoid gardens adjacent to building; Do not overwater. Repair plumbing leaks promptly. | Unlikely  | Minor                   | Low             |
| 11 | Foundation movement due to tree removal or planting  | Possible  | Minor to Major          | Moderate to High | Restrict tree planting to (and tree removal from) a distance from the house of 1.5x, 1x and 0.75x mature tree height for Class P, (H1, H2) and M sites respectively      | Unlikely  | Minor                   | Low             |
| 12 | Surface drainage   | Possible  | Minor                   | Moderate         | Divert surface drainage away from buildings to reticulated system  | Possible  | Insignificant           | Very Low        |
| 13 | Flooding or waterlogging   | Unlikely  | Medium                  | Low              | As for Issues 10 and 12  |   |                         |                 |
| 14 | Shallow groundwater seepages   | Unlikely  | Medium                  | Low              | Divert seepages with cut-off drains behind retaining walls, or in herring bone alignment diagonally down slope, away from buildings                                      | Unlikely  | Minor                   | Low             |
| 15 | Site contamination from previous activities  | Unlikely  | Minor to Medium         | Low              | Visual examination during construction. Removal or testing of suspect materials. May require outside advice.   | Unlikely  | Minor to Medium         | Low             |
| 16 | Earthquake risk  | Almost certain (magnitude <5); Likely (magnitude > 5) | Insignificant to Medium | Low to Moderate  | Accept risk. Risk applies to all Tasmanian houses to varying degrees depending on earthquake intensity, geology and house construction                                   | Almost certain (magnitude <5); Likely (magnitude > 5) | Insignificant to Medium | Low to Moderate |

1. The assessments are unavoidably subjective to varying degrees.


2. Further reading: AGS (2007c). Practice Notes Guidelines for Landslide Risk Management. Australian Geomechanics Vol 42 No 1 March 2007








**Attachment 2**  
**Title plan**





**Attachment 3**  
**Excavation logs of test pits**







| William C. Cromer Pty. Ltd. Environmental, engineering and groundwater geologists<br><a href="http://www.williamccromer.com/">http://www.williamccromer.com/</a>   |              |                                |       |               |             |   |   |                    |             | EG69B<br>Sheet 1 of 1         |                  |  |  |
|--|--------------|--------------------------------|-------|---------------|-------------|---|---|--------------------|-------------|-------------------------------|------------------|--|--|
| Project – Eastmans Green Subdivision, Newstead   |              |                                |       |               |             |   |   |                    |             | Location – Lot 69             |                  |  |  |
| Coordinates  |              | 514145mE<br>5411091mN          |       | Exposure type |             | Excavator test pit                                  |   | Date dug           |             | 12 June 2014                  |                  |  |  |
| Datum  |              | GDA94                          |       | Equipment     |             | 12t Caterpillar with 0.6m<br>GP bucket with 3 teeth |   | Date logged        |             | 12 June 2014                  |                  |  |  |
| RL   |              | 20.2m (Surveyed)               |       | Operator      |             | Harry Bracey  |   | Logged by          |             | W. C. Cromer                  |                  |  |  |
| Dimensions (m)   |              | Depth 3.0 Length 2.5 Width 0.7 |       | Checked by    |             | W. C. Cromer  |   |                    |             |                               |                  |  |  |
| 1<br>Penetration   | 2<br>Support | 3<br>Water                     | Notes | metres        | Graphic log | USCS  | Materials   | Moisture condition | Consistency | Strength                      |                  |  | Structure, geology and interpretation  |
|  |              |                                |       |               |             |   |   |                    |             | Hand penetrometer (kPa)       | Shear Vane (kPa) | Dynamic cone penetrometer (Blows per 100mm)                |  |
|  |              |                                |       | RL            | Depth       |   | Soil type, colour, plasticity or particle characteristics, secondary and minor components |                    |             | 25<br>50<br>100<br>200<br>400 |                  | 2<br>4<br>6<br>8<br>10<br>12<br>14<br>16<br>18<br>20<br>22 |  |
|  | None         | GNE                            |       |               | 0.5         | CH, SC  | Variable texture: CLAY, SAND: orange, grey; low to mod plasticity                         | M->PL              | St          |                               | 44kPa@0.3m       |  | Fill                                   |
|  |              |                                |       |               | 0.7         | SP  | Gravelly SAND: purple   | D                  | VD          |                               |                  |  |  |
|  |              |                                |       |               | 0.9         | SP  | SAND: grey  |                    | Fb-D        |                               |                  |  |  |
|  |              |                                |       |               | 1.1         | SC  | Clayey SAND: orange and grey  | M<PL               | VSt         |                               |                  |  | A soil horizon                         |
|  |              |                                |       |               | 1.3         | CH  | Sandy CLAY: orange with grey patches  | M<PL               | VSt         |                               | 170kPa@1.2m      |  | B soil horizon                         |
|  |              |                                |       |               | 1.5         |   |   |                    |             |                               | 228kPa@1.5m      |  |  |
|  |              |                                |       |               | 1.8         |   |   |                    |             |                               | 170kPa@1.8m      |  |  |
|  |              |                                |       |               | 2.0         | SC  | Clayey SAND: light yellowish grey   | M                  | Fb-D        |                               |                  |  | Extremely weathered Tertiary sandstone |
|  |              |                                |       |               | 2.5         |   |   |                    |             |                               |                  |  |  |
|  |              |                                |       |               | 3.0         |   | Abandoned 500Φ concrete pipe in gravel ; invert at 3.0m                                   |                    |             |                               |                  |  |  |
|  |              |                                |       |               | 3.0         |   | Hole terminated at required depth of 3.0m in Tertiary sandstone                           |                    |             |                               |                  |  |  |
|  |              |                                |       |               | 3.5         |   |   |                    |             |                               |                  |  |  |
|  |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |
|  |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |
|  |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |
|  |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |
|  |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |
|  |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |
|  |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |
| <p>40mm (Class H1) = ground surface movement estimated from test pit log and lss results in pit 69A</p>  |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |
| <p><b>Consistency</b> (silt, clay, sandy clay, silty clay) VS = Very soft (&lt;25kPa; exudes in fingers when squeezed); S = Soft (25-50kPa; easily penetrated by fist); F = Firm (50-100kPa; easily penetrated by thumb); St = Stiff (100-200kPa; indented by thumb, penetrated with difficulty); VSt= Very Stiff (200-400kPa; easily penetrated by thumbnail); H = Hard (&gt;400kPa; indented by thumbnail with difficulty); Fb = Friable (crumbles or powders when scraped by thumbnail)</p> <p><b>Relative density</b> (sand and gravel) VL = Very loose (ravelling); L = Loose (easy shovelling); MD = Medium dense (hard shovelling); D = Dense (picking); VD = Very dense (hard picking)</p> |              |                                |       |               |             |   |   |                    |             |                               |                  |  |  |





#### **Attachment 4**

#### **Site and test pit photographs**

The staff in these photographs is graduated in yellow and white sections each one metre long.  
The numbers on the staff are decimetres (tenths of a metre).

The main photograph depicts the soil profile in the test pit.  
Smaller photos (if present) show the materials excavated from the pit, the location of the pit in relation to roads, etc, and other aspects of interest as indicated.







## Attachment 5

(4 pages)


### Good and poor hillside construction practices

#### AGS Geoguide LR8 (Construction Practice)

##### HILLSIDE CONSTRUCTION PRACTICE

Sensible development practices are required when building on hillsides, particularly if the hillside has more than a low risk of instability (GeoGuide LR7). Only building techniques intended to maintain, or reduce, the overall level of landslide risk should be considered. Examples of good hillside construction practice are illustrated below.

#### EXAMPLES OF GOOD HILLSIDE CONSTRUCTION PRACTICE



##### WHY ARE THESE PRACTICES GOOD?

**Roadways and parking areas** - are paved and incorporate kerbs which prevent water discharging straight into the hillside (GeoGuide LR5).

**Cuttings** - are supported by retaining walls (GeoGuide LR6).

**Retaining walls** - are engineer designed to withstand the lateral earth pressures and surcharges expected, and include drains to prevent water pressures developing in the backfill. Where the ground slopes steeply down towards the high side of a retaining wall, the disturbing force (see GeoGuide LR6) can be two or more times that in level ground. Retaining walls must be designed taking these forces into account.

**Sewage** - whether treated or not is either taken away in pipes or contained in properly founded tanks so it cannot soak into the ground.

**Surface water** - from roofs and other hard surfaces is piped away to a suitable discharge point rather than being allowed to infiltrate into the ground. Preferably, the discharge point will be in a natural creek where ground water exits, rather than enters, the ground. Shallow, lined, drains on the surface can fulfil the same purpose (GeoGuide LR5).

**Surface loads** - are minimised. No fill embankments have been built. The house is a light weight structure. Foundation loads have been taken down below the level at which a landslide is likely to occur and, preferably, to rock. This sort of construction is probably not applicable to soil slopes (GeoGuide LR3). If you are uncertain whether your site has rock near the surface, or is essentially a soil slope, you should engage a geotechnical practitioner to find out.

**Flexible structures** - have been used because they can tolerate a certain amount of movement with minimal signs of distress and maintain their functionality.


**Vegetation clearance** - on soil slopes has been kept to a reasonable minimum. Trees, and to a lesser extent smaller vegetation, take large quantities of water out of the ground every day. This lowers the ground water table, which in turn helps to maintain the stability of the slope. Large scale clearing can result in a rise in water table with a consequent increase in the likelihood of a landslide (GeoGuide LR5). An exception may have to be made to this rule on steep rock slopes where trees have little effect on the water table, but their roots pose a landslide hazard by dislodging boulders.

Possible effects of ignoring good construction practices are illustrated on page 2. Unfortunately, these poor construction practices are not as unusual as you might think and are often chosen because, on the face of it, they will save the developer, or owner, money. You should not lose sight of the fact that the cost and anguish associated with any one of the disasters illustrated, is likely to more than wipe out any apparent savings at the outset.

##### ADOPT GOOD PRACTICE ON HILLSIDE SITES



## AUSTRALIAN GEOGUIDE LR8 (CONSTRUCTION PRACTICE) EXAMPLES OF **POOR** HILLSIDE CONSTRUCTION PRACTICE



### WHY ARE THESE PRACTICES POOR?

**Roadways and parking areas** - are unsurfaced and lack proper table drains (gutters) causing surface water to pond and soak into the ground.

**Cut and fill** - has been used to balance earthworks quantities and level the site leaving unstable cut faces and added large surface loads to the ground. Failure to compact the fill properly has led to settlement, which will probably continue for several years after completion. The house and pool have been built on the fill and have settled with it and cracked. Leakage from the cracked pool and the applied surface loads from the fill have combined to cause landslides.

**Retaining walls** - have been avoided, to minimise cost, and hand placed rock walls used instead. Without applying engineering design principles, the walls have failed to provide the required support to the ground and have failed, creating a very dangerous situation.

**A heavy, rigid, house** - has been built on shallow, conventional, footings. Not only has the brickwork cracked because of the resulting ground movements, but it has also become involved in a man-made landslide.

**Soak-away drainage** - has been used for sewage and surface water run-off from roofs and pavements. This water soaks into the ground and raises the water table (GeoGuide LR5). Subsoil drains that run along the contours should be avoided for the same reason. If felt necessary, subsoil drains should run steeply downhill in a chevron, or herring bone, pattern. This may conflict with the requirements for effluent and surface water disposal (GeoGuide LR9) and if so, you will need to seek professional advice.

**Rock debris** - from landslides higher up on the slope seems likely to pass through the site. Such locations are often referred to by geotechnical practitioners as "debris flowpaths". Rock is normally even denser than ordinary fill, so even quite modest boulders are likely to weigh many tonnes and do a lot of damage once they start to roll. Boulders have been known to travel hundreds of metres downhill leaving behind a trail of destruction.

**Vegetation** - has been completely cleared, leading to a possible rise in the water table and increased landslide risk (GeoGuide LR5).

### DON'T CUT CORNERS ON HILLSIDE SITES - OBTAIN ADVICE FROM A GEOTECHNICAL PRACTITIONER

More information relevant to your particular situation may be found in other Australian GeoGuides:



- GeoGuide LR1 - Introduction
- GeoGuide LR2 - Landslides
- GeoGuide LR3 - Landslides in Soil
- GeoGuide LR4 - Landslides in Rock
- GeoGuide LR5 - Water & Drainage
- GeoGuide LR6 - Retaining Walls
- GeoGuide LR7 - Landslide Risk
- GeoGuide LR9 - Effluent & Surface Water Disposal
- GeoGuide LR10 - Coastal Landslides
- GeoGuide LR11 - Record Keeping

The Australian GeoGuides (LR series) are a set of publications intended for property owners; local councils; planning authorities; developers; insurers; lawyers and, in fact, anyone who lives with, or has an interest in, a natural or engineered slope, a cutting, or an excavation. They are intended to help you understand why slopes and retaining structures can be a hazard and what can be done with appropriate professional advice and local council approval (if required) to remove, reduce, or minimise the risk they represent. The GeoGuides have been prepared by the Australian Geomechanics Society, a specialist technical society within Engineers Australia, the national peak body for all engineering disciplines in Australia, whose members are professional geotechnical engineers and engineering geologists with a particular interest in ground engineering. The GeoGuides have been funded under the Australian governments' National Disaster Mitigation Program.



### Generalised good and poor construction practices for hillsides in Launceston



These schematic cross sections apply to houses on hillsides on geologic materials called the Launceston Beds. See Attachment 3 of Part 2 of this report.





### Generalised good and poor hillside construction practices on fill

Natural scale





## Attachment 6 (2 pages) Important notes about this report

### Background information

William C Cromer Pty Ltd has been engaged by Ecoast Homes Pty Ltd to prepare site classification ("soil test") reports for about 50 lots in the Eastmans Green Subdivision.

The assessments are being done in accordance with Australian Standard 2870:2011 *Residential slabs and footings*, and draft Tasmanian guidelines<sup>1</sup> relating to the draft Tasmanian Landslide Code.

This individual AS2870 soil test report contains geotechnical information specific to the lot in question, and is freely available at <http://eastmansgreen.com.au/> It is PART 1 of the AS2870 site assessment for the lot.

Important geotechnical information is common to all lots in the subdivision. Rather than repeat this information in each individual report, it was thought preferable to provide it as a separate document (PART 2), freely available at <http://eastmansgreen.com.au/> and <http://www.williamccromer.com/>

**PART 1 and PART 2 together constitute the AS2870 site classification for this lot.**

### Design of footing systems for this site

Recommendations for a footing system in this report do not preclude the use of alternative footing systems based on sound engineering principles sensitive to the site.

### Implications for AS2870 reports from the draft Tasmanian Landslide Code and guidelines

There are Tasmania-wide implications for AS2870 site classifications if the draft Tasmanian Landslide Code<sup>2</sup> is adopted in its current form:

- All residential lots in the Medium landslide hazard band<sup>3</sup> will automatically be classified as Class P unless otherwise classified by a suitably qualified practitioner. Footings for Class P sites require certification by a suitably experienced engineer.
- In the Medium landslide hazard band, new buildings (or new extensions to an existing building) which result in a total final floor area greater than 200m<sup>2</sup> will require a Landslide Risk Management (LRM) report.

Most of the Eastmans Green Subdivision is in the Medium landslide hazard band (see Attachment 1 of PART 2). A general LRM has been completed for the subdivision as Attachment 4 in PART 2. Where appropriate, automatic Class P classifications for lots in the Medium landslide band in this subdivision have been amended.

### Refer to this report as:

Cromer, W. C. (2014). *Geotechnical summary, site classification and wind classification, Lot 69 Eastmans Green Subdivision, Newstead*. Unpublished report for Ecoast Homes Pty Ltd by William C. Cromer Pty. Ltd., 22 August 2014.

<sup>1</sup>Cromer, W. C. (2014). *Building for landslide: Geotechnical guidance for regulators and practitioners using the Tasmanian Landslide Code*. Report for the Tasmanian Department of Premier and Cabinet by William C. Cromer Pty. Ltd., June 2014).

<sup>2</sup> Available at [http://www.planning.tas.gov.au/\\_data/assets/pdf\\_file/0009/168948/Draft\\_Planning\\_Directive\\_-\\_Statewide\\_Codes.pdf](http://www.planning.tas.gov.au/_data/assets/pdf_file/0009/168948/Draft_Planning_Directive_-_Statewide_Codes.pdf)

<sup>3</sup> See Attachment 1 of *Geotechnical Notes to accompany AS2870 ("soil test") reports for individual lots, Eastmans Green Subdivision, Newstead*





### Dissemination of information is important

New geotechnical information is contained in this report. The information may be useful to regulators and other geotechnical practitioners. Dissemination of such knowledge is important.

Permission is hereby given by Ecoast Homes Pty Ltd, and William C. Cromer as author, for an electronic copy of this report to be distributed to or made available to interested parties, but only if it is distributed or made available in full. No responsibility is otherwise taken for its contents.

Permission is also given by Ecoast Homes Pty Ltd, and William C. Cromer as author, for hard copies of this report to be distributed to interested parties, but only if they are reproduced in colour, and only distributed in full. No responsibility is otherwise taken for the contents.

William C Cromer Pty Ltd may submit hard or electronic copies of this report to Mineral Resources Tasmania to enhance the geotechnical database of Tasmania.

This report is freely available at <http://eastmansgreen.com.au/> and <http://www.williamccromer.com/>

### Other reports on this subdivision

William C Cromer Pty Ltd produced detailed geotechnical reports (including landslide risk management, LRM) for Ecoast Homes Pty Ltd for the original Eastmans Green subdivision:

- Cromer, W. C. (2009). *Geotechnical assessment, 76 – lot subdivision, Penquite Road, Newstead*. (Unpublished report for ECoast Homes Pty Ltd by William C. Cromer Pty. Ltd., 7 April 2009; 137 pages), and
- Cromer, W. C. (2011). *Geotechnical Assessment Addendum Report, Eastman's Green subdivision, Penquite Road, Newstead*. (Unpublished report for ECoast Homes Pty Ltd by William C. Cromer Pty. Ltd., 22 May 2011; 33 pages)

Both are available at <http://eastmansgreen.com.au/> and <http://www.williamccromer.com/>

Notes about how Tasmanian practitioners should prepare AS2870 soil test reports for houses are available at <http://www.williamccromer.com/soil-testing-for-houses/>

#### WARNING

**Printed copies of this report must be reproduced in colour, and in full. No responsibility is otherwise taken for its contents.**

